

Kisent Template

NOTE

The labor crew cost in this report is based on an average crew make up with the wages, fringes and burdens based on the national averages for each trade. An actual project will be based on average labor rates for the specific region in which the project is to be constructed.

Table of Contents

October 12, 2007

- 1 Project Directory
 - 2 Clarifications
- 3 Pending Item List
- 4 Summary of Project Definitions
- **5 Program Space Project Definitions**
 - 6 Core Space Project Definitions
 - 7 Program Space Criteria Sheets
 - 8 Core Space Criteria Sheets
 - 9 Detailed Estimate
 - 10 Labor Crew Report
 - 11 Detailed Estimate Summary

PROJECT DIRECTORY

Clarifications and Qualifications

October 12, 2007

Executive Summary

Project Scope

This project consists of the interior demolition of approximately 1,000 square feet in an existing building to create the space for new offices. In the core of the building approximately 200 square feet of an existing public corridor will also be renovated.

The elements that comprise this submittal are the project definitions, design criteria for each of the definitions, clarifications and qualifications, a pending item list and the detailed estimate and summary.

The project definitions are divided into the following sections:

Program Space - Owner required rooms and areas

Core Space - corridors and public areas.

The prices in the estimated cost of construction include the following markups and adjustments:

Sales Tax on the Material

Subcontractor Direct and Indirect Job Costs

Subcontractor Overhead and Profit

General Contractor or Prime Contractor General Conditions

General Contractor or Prime Contractor Overhead and Profit

Construction Bonds

Design Contingency

Exclusions

The following items are NOT included in this project:

Hazardous Abatement

Loose / Not Built-In Furniture

Art Work

Land and Real Estate Costs

Design Fees

Legal and Accounting Fees

Construction Manager's Fees

Construction Contingency

Interior Tenant Fit-Out Clarifications and Qualifications

October 12, 2007

ARCHITECTURAL

General Overview

The following is a general overview of the architectural finishes for the various rooms in this project:

Open Office - carpet floor covering, painted gypsum board walls, wood doors and acoustic tile ceilings.

Private Offices - same as Open Office with wall finish and lighting upgrades.

Corridors - high traffic carpet floor covering, painted gypsum board walls and acoustic tile ceilings.

Space Definitions and Design Criteria

Space and functional definitions are included in this submittal for the Program and Core areas along with individual criteria sheets for each space.

Pending Item List

October 12, 2007

The following is a list of items that may be required but are currently not included.

Program Space

Interior Demolition	Program Space Line #	1
Demolition - Selective Doors		
Demolition - Selective Millwork & Casework		
Private Office	Program Space Line #	2
Wall Finish - Wood Panel		
VCT & Vinyl Sheet Flooring		
Casework 1		
Voice - Data Jacks, Plates & Cable		
Reception Area	Program Space Line #	3
Downlights & Wall Washers - Compact Fluo	rescents	
Voice - Data Jacks, Plates & Cable		
Open Office Area	Program Space Line #	4
Downlights & Wall Washers - Compact Fluo	rescents	
Voice - Data Jacks, Plates & Cable		

Core Space

No Pending Items

Summary of Project Definitions

October 12, 2007

	Program	n Space	
Defined Area		1,000	
Gross Area		1,200	
Net Gross Factor		120%	
Approximate Cost		\$75,182	\$62.65 / SQFT
Gen. Cond. OH&P	15%	\$11,277	
Contingencies	10%	\$8,646	
Approx. Cost with Markup		\$95,105	\$79.25 / SQFT

	Core	Space	
Defined Area		200	Defined Area is
Defined Core & Program Area		1,200	Balanced with the Gross
Slab Openings / Voids		0	
Program Gross Area - Openings		1,200	
Approximate Cost		\$14,784	\$12.32 / SQFT
Gen. Cond. OH&P	15%	\$2,218	
Contingencies	10%	\$1,700	
Approx. Cost with Markup		\$18,701	\$15.58 / SQFT

	Tot	als		
Defined Area		1,200		
Gross Area		1,200		
Net Gross Factor		100%		
Approximate Cost		\$89,966	\$74.97	/ SQFT
Gen. Cond. OH&P	15%	\$13,495		
Contingencies	10%	\$10,346		
Approx. Cost with Markup		\$113,807	\$94.84	/ SQFT

Interior Tenant Fit-Out Project Definitions

Program Space Sheet 1 of 1 October 12, 2007

Re	ef			Size		C	esign P	arameters				D	esign P	arameters				esign P	arameters			Approx.
#		Name of Space	Qty	of Each		eter # 1			eter # 2		Paran	neter # 3		Parameter	r # 4	Parai	neter # 5		Param	eter # 6		Cost
1	lr	nterior Demolition	1		Complete Interior Demolition	1,000.	SQFT	Temporary Dust Barrier	50.	LNFT	Partition Demolition		SQFT	Ceiling Demolition	SQI	Т						\$8,201
2	Р	Private Office	2	100	Area / Size	100.	SQFT	Partition Height	11.	VLF	Ceiling Height	9.	VLF	Number of Doors	1. EAC	H Room Perimeter	45.	LNFT				\$14,260
3	R	Reception Area	1	100	Area / Size	100.	SQFT	Partition Height	11.	VLF	Ceiling Height	9.	VLF	Number of Doors	1. EAC	H Room Perimeter	45.	LNFT	Reception Desk Length	6.	LNFT	\$15,976
4	c	Open Office Area	1	700	Area / Size	700.	SQFT	Partition Height	11.	VLF	Ceiling Height	9.	VLF	Number of Doors	2. EAG	H Room Perimeter	119.	LNFT				\$36,746

Interior Tenant Fit-Out Project Definitions

Core Space Sheet 1 of 1 October 12, 2007

Ref	f			Size			Design Pa	rameters				D	esign P	arameters					Design Pa	arameters		Approx.
#		Name of Space	Qty	of Each	Param	neter # 1		Param	eter # 2		Param	eter # 3		Param	eter # 4		Param	eter # 5		Param	eter # 6	Cost
1	С	Core Demolition	1		Complete Interior Demolition		SQFT	Temporary Dust Barrier	10.		Partition Demolition	240.	SQFT	Ceiling Demolition	200.	SQFT						\$1,330
2	Р	Public Corridor	1	200	Area / Size	200.	SQFT	Partition Height	11.	VLF	Ceiling Height	9.	VLF	Number of Doors	1.	EACH	Room Perimeter	64.	LNFT			\$13,454

							Program - 1
Project Name	Interior Te	enant F	it-Out				
Description / Space	Interior De	emolitic	on				October 12, 2007
	1,000.	SQFT	Complete Interior Demolition		Project I		owns
ters	50.	LNFT	Temporary Dust Barrier	Base / Options	Base Desig		
ille.		<u> </u>	Partition Demolition	Area Not Used	Ground Flo	or	
ara		SQFI	Ceiling Demolition	Space Description	Interior De	molition	1
_				opuse Description	Interior Be	montion	
Quantity / Multiplier	1.			Approx. Co	ost		\$8,201
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection
Demolition - General Interior	1,000.	SQFT	Demolish Complete Building Interior (Gutting)				
Temporary Dust Barrier	50.	LNFT	Erect & Remove Temporary Construction Partition				
			- union				
Demolition - Selective Walls &		SQFT	Remove Stud Wall or Furring with Gypsum Board				
Partitions Demolition - Additional			None Required				
Selective Walls & Partitions							
Domolition Colonia Oction		2057	Romaya Cailing				
Demolition - Selective Ceilings Demolition - Additional		SQFT	Remove Ceiling				
Selective Ceilings			None Required				
Demolition - Selective Doors			Not Selected				
Demolition - Additional Selective Doors			None Required				
Demolition - Selective Flooring			None Required				
Demolition - Selective Windows			None Required				
Demolition - Selective Millwork & Casework			Not Selected				
Demolition - Misc Selective			None Required				
Concrete Saw Cutting			None Required				
Demolition - Slabs on Grade			·				
Demolition - Slabs on Grade Demolition - Selective			None Required				
Structural			None Required				
Demolition - Roofing			None Required				
Kisent Budgetware & Est	imating Sy	stem®		EZ Model Fil	le: Selective De	emolition	

		Program - 1
Project Name	Interior Tenant Fit-Out	
Description / Space	Interior Demolition	October 12, 2007
	Comments and Clarifications	
1.	The owner is responsible for removing all furniture and belongings prior to the start of con	struction.
2.	All demolition and removal of debris shall be done on weekends or after normal business	hours.
		I
		I
		I
		I
		I
		I
		I
	imating System®	

Project Name	Interior Te	nant F	it-Out				Program - 2		
Description / Space	Private Of	fice					October 12, 2007		
Везоприон г орасс	100.		Area / Size		Project E	Breakd	,		
ဖွ	11.	VLF	Partition Height	Base / Options	Base Desid		0.1115		
ete	9.	VLF	Ceiling Height	Area	Ground Flo				
am	1.	EACH	Number of Doors	Not Used					
	45.	LNFT	Room Perimeter	Space Description	Private Offi	ice			
Quantity / Multiplier	2.			Approx. Cost			\$14,260		
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection		
Wall Framing - Interior Metal Studs	495.	SQFT	Metal Stud Wall - 25 ga. Non-Load Bear 3-5/8" W - 24" OC	Additional Door Hardware			None Required		
Gypsum Board on Walls	495.	SQFT	5/8" Standard Gypsum Board on Walls with Level 4 Finishing	Adder for SideLights			None Required		
Additional Gypsum Board on Walls			None Required	Glazing Window Frames			None Required		
Beam & Soffit Framing with Gypsum Board			None Required	Glazing - Safety, Security & Misc Glass			None Required		
Column Framing with Gypsum Board			None Required	MISO CIESS					
Juanu				Casework 1			Not Selected		
Wall Finish - Wood Panel			Not Selected	Casework 2			None Required		
Wall Finish - Paint & Wall Coverings	395.	SQFT	Painting - Primer + 2 Finish Coats - Brush / Roller - Smooth Surface	Casework 3			None Required		
Additional Wall Finish - Paint & Wall Coverings	100.	SQFT	Vinyl Wall Covering - 20 oz. Medium Weight - Decorative Pattern	Casework - Work Surface or Counter Top			None Required		
Carpet Floor Covering	100.	SQFT	Carpet - Commercial Grade - Medium	Supply Air Diffuser with Flex	1	EACH	12" x 12" Diffuser in 24" x 24" Lay In Panel + Flex Duct & Tap		
Carpet Pad	100.	SQFT	Duty Carpet Pad - Rebond (Bonded Urethane	Return Air Grille	1	EACH	Aluminum Return Air Grille - Plenum		
VCT & Vinyl Sheet Flooring			Foam) - Medium Duty (6 LB) Not Selected				No Duct - 18" x 18"		
Wood & Laminate Floors			None Required	Fluorescent Parabolics & Recessed Indirect	2	EACH	2' x 4' - 3 Lamp Commercial Direct / Indirect Fluorescent Lav In		
Marble - Granite - Quarry Tile Floors			None Required	Ceiling Mounted Fluorescent Light			None Required		
Wall Cove & Base	45.	LNFT	Vinyl or Rubber Base125" Thick - 4" High	Downlights & Wall Washers - Compact Fluorescents			None Required		
Ceiling Tile - Standard with Suspended Grid	1		None Required	Switches with Plates	1		None Required		
Ceiling Tile - Fire Rated with Suspended Grid	100.	SQFT	15/16" T Bar Suspended Ceiling - Tegular Tile - 2' x 2' Fire Rated Grid	Switches - Occupancy Sensor	1	EACH	Occupancy Sensor - Wall Mtd - Infrared - with Switch		
Ceiling - Gypsum Board on Metal Framing			None Required	Receptacles with Plates	4	EACH	Duplex Receptacle with Plastic Plate Spec Grade - 20A		
Ceiling Finish - Painting			None Required	Additional Receptacles with Plates	1	EACH	2 Gang Iso-Gr. Duplex Recept. with Plastic Plate - Spec Grade - 20A		
				Receptacles with Floor Boxes & Poke Thrus			None Required		
Fiberglass Insulation	100	SQFT	Unfaced Fiberglass Non-Rigid Insulation - 3-1/2" Thick	Power Connection for Partition or Furniture			None Required		
Acoustical Sound Batt	495	SQFT	Acoustical Glass Fiber Batt - Unfaced - 3-1/2" Thick	Electric Rough-In Box with Conduit & Wire	8	EACH	Rough In Box, Ring & 15' of 3/4" EN St*Comp Ftgs & Wire		
Hollow Core Steel Door			None Required	Voice - Data Jacks, Plates & Cable			Not Selected		
Additional Hollow Core Steel Door			None Required	Additional Voice - Data Jacks, Plates & Cable			None Required		
Solid Core Wood Door	1	EACH	Single Wood Door, Frame & Lockset- Oak- 3'-0" x 6'-8" or 7'-0"	Communication Rough-In Box & Conduit	1	EACH	Comm. Rough-In Box - 25' of 3/4" E St-SS Ftgs & Pull String		
Additional Solid Core Wood Door			None Required	Communication Rough-In for Partition or Furniture			None Required		
Additional Door Hardware			None Required						

		Program - 2
Project Name Description / Space	Interior Tenant Fit-Out	
Description / Space	Private Office	October 12, 2007
	Comments and Clarifications	
Kisent Budgetware & Es	imating System [®]	

Droinot Name	Interior Te	nort -	The Court				Program - 3
Project Name			it-Out				
Description / Space	Reception	1	T				October 12, 2007
(0	100.		Area / Size		Project E		owns
ters	11.	VLF	Partition Height	Base / Options	Base Desig		
Ше	9.	VLF	Ceiling Height	Area	Ground Flo	or	
ara	1. 45.		Number of Doors Room Perimeter	Not Used Space Description	Dagantian	A ===	
Д.	6.		Reception Desk Length	Space Description	Reception	Alea	
Quantity / Multiplier	1.	LINI	INECEPTION DESK LENGTH	Approx. Cost	_		\$15.976
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection
Wall Framing - Interior Metal	495.	SQFT	Metal Stud Wall - 25 ga. Non-Load Bear.	Additional Door Hardware	Q.i,	O/IVI	None Required
Studs			- 3-5/8" W - 24" OC 5/8" Standard Gypsum Board on Walls				Solid Core Wood Door - Add for
Gypsum Board on Walls	495.	SQFT	with Level 4 Finishing	Adder for SideLights	2	EACH	Sidelight - Interior Glass
Additional Gypsum Board on Walls			None Required	Glazing Window Frames			None Required
Beam & Soffit Framing with Gypsum Board	6.	LNFT	Beam / Soffit - 1/2" Gyp. Bd Mtl Frame - Lvl 4 Finish - Medium	Glazing - Safety, Security & Misc Glass			None Required
Column Framing with Gypsum Board			None Required	Aluminum Windows - Slider	1	EACH	Alum. Window - Slider - Std. Glass - Comm. Gr 36" x 36"
Wall Finish - Wood Panel			None Required	Casework 1	6	LNFT	Plastic Laminated Casework - Speci Order - Base Cabinet
Wall Finish - Paint & Wall Coverings	495.	SQFT	Painting - Primer + 2 Finish Coats - Brush / Roller - Smooth Surface	Casework 2	6	LNFT	Plastic Laminated Casework - Speci Order - Wall Cabinet
Additional Wall Finish - Paint & Wall Coverings			None Required	Casework - Work Surface or Counter Top	6	LNFT	Solid Plastic / Polymer Work Surface Counter Top - No Backsplash
Carpet Floor Covering	100.	SQFT	Carpet - Commercial Grade - Heavy Duty	Supply Air Diffuser with Flex	1	EACH	12" x 12" Diffuser in 24" x 24" Lay In Panel + Flex Duct & Tap
Carpet Pad	100.	SQFT	Carpet Pad - Rebond (Bonded Urethane	Return Air Grille	1	EACH	Aluminum Return Air Grille - Plenum
/CT & Vinyl Sheet Flooring			Foam) - Heavy Duty (8 LB) None Required				No Duct - 18" x 18"
Wood & Laminate Floors			None Required	Fluorescent Parabolics &	2	EACH	2' x 4' - 3 Lamp 3" Parabolic
Marble - Granite - Quarry Tile			None Required	Recessed Indirect Ceiling Mounted Fluorescent			Fluorescent Lay In None Required
Floors Wall Cove & Base	45.	LNFT	Vinyl or Rubber Base125" Thick - 4" High	Light Downlights & Wall Washers - Compact Fluorescents			Not Selected
Ceiling Tile - Standard with			None Required	Switches with Plates			None Required
Ceiling Tile - Fire Rated with Suspended Grid	100.	SQFT	15/16" T Bar Suspended Ceiling - Tegular Tile - 2' x 2' Fire Rated Grid	Switches - Occupancy Sensor	1	EACH	Occupancy Sensor - Wall Mtd - Infrared - with Switch
Ceiling - Gypsum Board on Metal Framing			None Required	Receptacles with Plates	4	EACH	Duplex Receptacle with Plastic Plate Spec Grade - 20A
Ceiling Finish - Painting			None Required	Additional Receptacles with Plates	1	EACH	2 Gang Iso-Gr. Duplex Recept. with Plastic Plate - Spec Grade - 20A
				Receptacles with Floor Boxes & Poke Thrus	1	EACH	Iso.Gr. Dbl. Duplex Receptacle - Fir Rated Poke Thru with Core Drill
Fiberglass Insulation	100	SQFT	Unfaced Fiberglass Non-Rigid Insulation - 3-1/2" Thick	Power Connection for Partition or Furniture			None Required
Acoustical Sound Batt	495	SQFT	Acoustical Glass Fiber Batt - Unfaced - 3- 1/2" Thick	Electric Rough-In Box with Conduit & Wire	9	EACH	Rough In Box, Ring & 15' of 3/4" EN St*Comp Ftgs & Wire
Hollow Core Steel Door			None Required	Voice - Data Jacks, Plates & Cable			Not Selected
Additional Hollow Core Steel			None Required	Additional Voice - Data			None Required
Door Solid Core Wood Door	1	EACH	Double Wood Door, Frame, Lockset & Closer - Oak - 6'-0" x 8'-0"	Jacks, Plates & Cable Communication Rough-In Box & Conduit	1	EACH	Comm. Rough-In Box - 25' of 3/4" El St-SS Ftgs & Pull String
Additional Solid Core Wood			None Required	Communication Rough-In for Partition or Furniture	1	EACH	Communication Connection Rough-l to Furniture - Poke Thru Floor Box
			None Required	. datalon of Familiaro			to a strikero i oke i iliu i looi box

Project Name	Interior Te	nant F	it-Out				Program - 4
Description / Space	Open Offic						October 12, 2007
Description / Opace	700.		Area / Size		Project E	Breakd	,
ıσ	11.	VLF	Partition Height	Base / Options	Base Design		owns
eter	9.	VLF	Ceiling Height	Area	Ground Flo		
ame	2.		Number of Doors	Not Used	Cround 1 ic		
Pari	119.		Room Perimeter	Space Description	Open Offic	e Area	
Quantity / Multiplier	1.			Approx. Cost			\$39,335
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection
Wall Framing - Interior Metal Studs	1,309.	SQFT	Metal Stud Wall - 25 ga. Non-Load Bear. - 3-5/8" W - 24" OC	Additional Door Hardware			None Required
Gypsum Board on Walls	1,309.	SQFT	5/8" Standard Gypsum Board on Walls with Level 4 Finishing	Adder for SideLights	2	EACH	Solid Core Wood Door - Add for Sidelight - Interior Glass
Additional Gypsum Board on			None Required	Glazing Window Frames			None Required
Walls Beam & Soffit Framing with Gypsum Board	80.	LNFT	Beam / Soffit - 5/8" Fire Res. Gyp. Bd Lvl 4 Fin Mtl Frame - Medium	Glazing - Safety, Security & Misc Glass			None Required
Column Framing with Gypsum Board	40.	VLF	24" Sq. Column Frame - 3-5/8" Mtl Studs - 5/8" Fire Res. Gyp. Bd Lvl 4 Fin.				
Douid			ого т не res. сур. Du LVI 4 FIII.	Casework 1	10	LNFT	Plastic Laminated Casework - Common Stock - Base Cabinet
Wall Finish - Wood Panel			None Required	Casework 2	10	LNFT	Plastic Laminated Casework - Common Stock - Wall Cabinet
Wall Finish - Paint & Wall Coverings	1,309.	SQFT	Painting - Primer + 2 Finish Coats - Brush / Roller - Smooth Surface	Casework 3			None Required
Additional Wall Finish - Paint & Wall Coverings			None Required	Casework - Work Surface or Counter Top	10	LNFT	Plastic Laminated Work Surface / Counter Top - No Backsplash
				Supply Air Diffuser with Flex			12" x 12" Diffuser in 24" x 24" Lay In
Carpet Floor Covering	700.	SQFT	Carpet - Commercial Grade - Heavy Duty	Duct Direct	3	EACH	Panel + Flex Duct & Tap
Carpet Pad	700.	SQFT	Carpet Pad - Rebond (Bonded Urethane Foam) - Heavy Duty (8 LB)	Return Air Grille	2	EACH	Aluminum Return Air Grille - Plenum No Duct - 18" x 18"
VCT & Vinyl Sheet Flooring			None Required				
Wood & Laminate Floors			None Required	Fluorescent Parabolics & Recessed Indirect	10	EACH	2' x 4' - 3 Lamp 3" Parabolic Fluorescent Lay In
Marble - Granite - Quarry Tile Floors			None Required	Ceiling Mounted Fluorescent Light			None Required
Wall Cove & Base	119.	LNFT	Vinyl or Rubber Base125" Thick - 4" High	Downlights & Wall Washers - Compact Fluorescents			Not Selected
Ceiling Tile - Standard with Suspended Grid	1		None Required	Switches with Plates			None Required
Ceiling Tile - Fire Rated with Suspended Grid	700.	SQFT	15/16" T Bar Suspended Ceiling - Tegular Tile - 2' x 2' Fire Rated Grid	Switches - Occupancy Sensor	1	EACH	Occupancy Sensor - Wall Mtd - Infrared - with Switch
Ceiling - Gypsum Board on Metal Framing			None Required	Receptacles with Plates	10	EACH	Duplex Receptacle with Plastic Plate Spec Grade - 20A
Ceiling Finish - Painting			None Required	Additional Receptacles with Plates	1	EACH	2 Gang Iso-Gr. Duplex Recept. with Plastic Plate - Spec Grade - 20A
				Receptacles with Floor Boxes & Poke Thrus			None Required
Fiberglass Insulation	700	SQFT	Unfaced Fiberglass Non-Rigid Insulation - 3-1/2" Thick	Power Connection for Partition or Furniture	2	EACH	Power Connection to Furniture / Partition - Power Pole
Acoustical Sound Batt	1309	SQFT	Acoustical Glass Fiber Batt - Unfaced - 3- 1/2" Thick	Electric Rough-In Box with Conduit & Wire	24	EACH	Rough In Box, Ring & 15' of 3/4" EM St*Comp Ftgs & Wire
Hollow Core Steel Door			None Required	Voice - Data Jacks, Plates & Cable			Not Selected
Additional Hollow Core Steel Door			None Required	Additional Voice - Data Jacks, Plates & Cable			None Required
Solid Core Wood Door	2	EACH	Single Wood Door, Frame, Lockset & Closer- Birch- 3'-0" x 6'-8" or 7'-0"	Communication Rough-In Box & Conduit	4	EACH	Comm. Rough-In Box - 25' of 3/4" EI St-SS Ftgs & Pull String
Additional Solid Core Wood Door			None Required	Communication Rough-In for Partition or Furniture	2	EACH	Communication Connection Rough-I to Furniture - Tele Pole
Additional Door Hardware			None Required				

							Core - 1
Project Name	Interior Te	enant F	it-Out				
Description / Space	Core Dem	olition					October 12, 2007
		SQFT	Complete Interior Demolition		Project	Breakd	owns
ers	10.	LNFT	Temporary Dust Barrier	Base / Options	Base Desi	gn	
met	240.	SQFT	Partition Demolition	Area	Ground Flo	or	
arai	200.	SQFT	Ceiling Demolition	Not Used			
ů.				Space Description	Core Dem	olition	
Quantity / Multiplier	1.			Approx. Co	st		\$1,330
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection
Demolition - General Interior		SQFT	Demolish Complete Building Interior (Gutting)				
Temporary Dust Barrier	10.	LNFT	Erect & Remove Temporary Construction Partition				
Demolition - Selective Walls &	240.	SQFT	Remove Stud Wall or Furring with				
Partitions Demolition - Additional	240.	OQI I	Gypsum Board				
Selective Walls & Partitions			None Required				
Demolition - Selective Ceilings	200.	SQFT	Remove Ceiling				
Demolition - Additional Selective Ceilings			None Required				
Demolition - Selective Doors Demolition - Additional	2.	EACH	Remove Single Door & Frame				
Selective Doors			None Required				
Demolition - Selective Flooring	200.	SOFT	Remove Vinyl Composition Tile (VCT)				
Demolition - Selective Windows			None Required				
Demolition - Selective Millwork & Casework			None Required				
Demolition - Misc Selective			None Required				
Concrete Saw Cutting			None Required				
Demolition - Slabs on Grade			None Required				
Demolition - Selective Structural			None Required				
Demolition - Roofing			None Required				
Kisent Budgetware & Est	imating Sv	stem ®		EZ Model File	: Selective De	emolition	

Project Name	Interior To	nant F	ït-Out				Core - 2		
	Interior Tenant Fit-Out								
Description / Space		ublic Corridor October 1.							
	200.	SQFT	Area / Size		Project I		owns		
ters	11.	VLF	Partition Height	Base / Options	Base Desig				
ıme	9.	VLF	Ceiling Height	Area Not Used	Ground Flo	oor			
ara	64.	EACH	Number of Doors Room Perimeter	Space Description	Public Cor	ridor			
<u> </u>	04.	LINI	IXOUTH F ETITIFETED	Space Description	Fublic Con	3 Comuci			
Quantity / Multiplier	1.			Approx. Cost			\$13,454		
System	Qty	U/M	Criteria Selection	System	Qty	U/M	Criteria Selection		
Wall Framing - Interior Metal	704.	SQFT	Metal Stud Wall - 25 ga. Non-Load Bear. - 3-5/8" W - 24" OC	Additional Door Hardware			None Required		
Gypsum Board on Walls	704.	SQFT	5/8" Fire Resistant Gypsum Board on Walls with Level 4 Finishing	Adder for SideLights			None Required		
Additional Gypsum Board on	704.	SQFT	5/8" Fire Resistant Gypsum Board on	Glazing Window Frames			None Required		
Walls Beam & Soffit Framing with	104.	53,1	Walls with Level 2 Finishing None Required	Glazing - Safety, Security &			·		
Gypsum Board Column Framing with Gypsum	-			Misc Glass			None Required		
Board Board			None Required	0 1 1 2 2 2			101 101 PW		
				Supply Air Diffuser with Flex Duct	1	EACH	12" x 12" Diffuser in 24" x 24" Lay In Panel + Flex Duct & Tap		
Wall Finish - Wood Panel			None Required	Return Air Grille	1	EACH	Aluminum Return Air Grille - Plenum No Duct - 18" x 18"		
Wall Finish - Paint & Wall Coverings	704.	SQFT	Painting - Primer + 2 Finish Coats - Brush / Roller - Smooth Surface						
Additional Wall Finish - Paint & Wall Coverings			None Required	Fluorescent Parabolics & Recessed Indirect	3	EACH	2' x 4' - 2 Lamp 3" Parabolic Fluorescent Lay In		
				Ceiling Mounted Fluorescent Light			None Required		
Carpet Floor Covering	200.	SQFT	Carpet - Commercial Grade - Heavy Duty	Downlights & Wall Washers - Compact Fluorescents			None Required		
Carpet Pad	200.	SQFT	Carpet Pad - Rebond (Bonded Urethane Foam) - Heavy Duty (8 LB)						
VCT & Vinyl Sheet Flooring			None Required	Switches with Plates			None Required		
Wood & Laminate Floors			None Required	Switches - Occupancy Sensor	1	EACH	Occupancy Sensor - Ceiling Mtd - Infrared - Self Contained		
Marble - Granite - Quarry Tile Floors			None Required	Receptacles with Plates	3	EACH	Duplex Receptacle with Plastic Plate Spec Grade - 20A		
Wall Cove & Base	64.	LNFT	Vinyl or Rubber Base125" Thick - 4" High	Additional Receptacles with Plates			None Required		
				Receptacles with Floor Boxes & Poke Thrus			None Required		
Ceiling Tile - Standard with Suspended Grid			None Required	Electric Rough-In Box with Conduit & Wire	7	EACH	Rough In Box, Ring & 20' of 3/4" EN St*Comp Ftgs & Wire		
Ceiling Tile - Fire Rated with Suspended Grid	200.	SQFT	15/16" T Bar Suspended Ceiling - Tegular Tile - 2' x 2' Fire Rated Grid	Conduit & Wille			or south rigg a mile		
Ceiling - Gypsum Board on			None Required	Voice - Data Jacks, Plates &			None Required		
Metal Framing Ceiling Finish - Painting			None Required	Cable Additional Voice - Data			None Required		
				Jacks, Plates & Cable Communication Rough-In			None Required		
Fiberglass Insulation	200	SQFT	Unfaced Fiberglass Non-Rigid Insulation -	Box & Conduit					
Acoustical Sound Batt		SQFT	3-1/2" Thick Acoustical Glass Fiber Batt - Unfaced - 3-						
Journa Datt	7.04	- CQ1 1	1/2" Thick						
Hollow Core Steel Door	1	EACH	Double H.C. Steel Door + Frame, Panic						
Additional Hollow Core Steel	 	LAUIT	Bar & Closer - 6'-0" x 8'-0" None Required						
Door Solid Core Wood Door			None Required						
Additional Solid Core Wood			None Required						
Door Additional Door Hardware									
Additional Door Hardware Kisent Budgetware & Est			None Required	EZ Model File:					

Lombard, Illinois Date: 10/12/07

Description	Quantity	U/M	Unit Price	Unit Price Ext
02 - SITEWORK				
Demolish Complete Building Interior (Gutting)	1000 \$		\$6.54	\$6,540.00
Erect & Remove Temporary Construction Partition		NFT	\$33.22	\$1,993.20
Remove Stud Wall or Furring with Gypsum Board		SQFT	\$1.96	\$470.40
Remove Ceiling		SQFT	\$0.99	\$198.00
Remove Single Door & Frame		EACH	\$65.48	\$130.96
Remove Vinyl Composition Tile (VCT)	200 3	SQFT	\$0.99	\$198.00 \$9,530.56
06 - WOOD & PLASTICS	0.1	NET	©540.00	¢2.072.00
Plastic Laminated Casework - Special Order - Avg. Cost - Base Cabinet		_NFT _NFT	\$512.33	\$3,073.98
Plastic Laminated Casework - Special Order - Avg. Cost - Wall Cabinet Solid Plastic / Polymer Work Surface / Counter Top - No Backsplash		_NFT _NFT	\$388.79 \$127.66	\$2,332.74
Plastic Laminated Casework - Common Stock - Avg. Cost - Base Cabinet		_NFT	\$371.82	\$765.96 \$3,718.20
Plastic Laminated Casework - Common Stock - Avg. Cost - Base Cabinet Plastic Laminated Casework - Common Stock - Avg. Cost - Wall Cabinet		_NFT	\$283.41	\$2,834.10
Plastic Laminated Work Surface / Counter Top - No Backsplash		_NFT	\$106.59	\$1,065.90
	10.1		Ψ100.00 <u> </u>	\$13,790.88
07 - THERMAL & MOISTURE PROTECTION Unfaced Fiberglass Non-Rigid Insulation - 3-1/2" Thick	1200 \$	SOFT	\$0.70	\$840.00
	1200 (Jaii	φο.70	\$840.00
08 - DOORS AND WINDOWS Double Hollow Core Steel Door with Frame, Panic Bar & Closer - 6'-0" x 8'-0"	1 [EACH	\$3,848.33	\$3,848.33
Double Solid Core Wood Door, Frame, Lockset & Closer - Oak - 6'-0" x 8'-0"		EACH	\$1,641.99	\$1,641.99
Solid Core Wood Door - Add for Sidelight - Interior Glass		EACH	\$317.35	\$1,269.40
Single Solid Core Wood Door, Frame & Lockset - Oak - 3'-0" x 6'-8" or 7'-0"		EACH	\$675.34	\$1,350.68
Single Solid Core Wood Door, Frame, Lockset & Closer - Birch - 3'-0" x 6'-8" or 7'-0"		EACH	\$945.90	\$1,891.80
Aluminum Window - Slider - Std. Glass - Commercial Grade - 36" x 36"		EACH	\$340.32	\$340.32
				\$10,342.52
09 - FINISHES Metal Stud Wall - 25 ga. Non-Load Bear 3-5/8" W - 24" OC	3498 \$	SQFT	\$1.25	\$4,372.50
Beam / Soffit Framing - 1/2" Gyp. Bd Level 4 Finish on Metal Framing - Medium		NFT	\$20.82	\$124.92
Beam / Soffit Framing - 5/8" Fire Res. Gyp. Bd Lvl 4 Fin. on Mtl Framing - Medium	80 I	NFT	\$21.31	\$1,704.80
Column Framing - 5/8" Fire Res. Gyp. Bd Lvl 4 Fin. on 3-5/8" Mtl Studs - 24" Sq.	40 \	/LF	\$35.77	\$1,430.80
5/8" Fire Resistant Gypsum Board on Walls with Level 4 Finishing	704 \$	SQFT	\$2.03	\$1,429.12
5/8" Fire Resistant Gypsum Board on Walls with Level 2 Finishing	704 \$	SQFT	\$1.67	\$1,175.68
5/8" Standard Gypsum Board on Walls with Level 4 Finishing	2794 \$	SQFT	\$1.94	\$5,420.36
15/16" T Bar Suspended Ceiling - Tegular Tile - 2' x 2' Fire Rated Grid	1200 \$	SQFT	\$3.84	\$4,608.00
Acoustical Glass Fiber Batt - Unfaced - 3-1/2" Thick	3498 \$		\$0.68	\$2,378.64
Vinyl or Rubber Base125" Thick - 4" High	318 l		\$2.43	\$772.74
Carpet - Commercial Grade - Heavy Duty	1000 \$		\$4.77	\$4,770.00
Carpet Pad - Rebond (Bonded Urethane Foam) - Heavy Duty (8 LB)	1000 \$		\$1.10	\$1,100.00
Carpet - Commercial Grade - Medium Duty		SQFT	\$3.61	\$722.00
Carpet Pad - Rebond (Bonded Urethane Foam) - Medium Duty (6 LB)		SQFT	\$0.86	\$172.00
Painting - Primer + 2 Finish Coats - Brush / Roller - Smooth Surface	3298 \$		\$1.12	\$3,693.76
Vinyl Wall Covering - 20 oz. Medium Weight - Decorative Pattern	200 \$	SQFT	\$2.83	\$566.00 \$34,441.32
15 - MECHANICAL	7.	- 4 01 1	0054.40	
12" x 12" Diffuser in 24" x 24" Lay In Panel with Flex Duct & Tap		EACH	\$351.42	\$2,459.94 \$561.84
Aluminum Return Air Grille - 18" x 18"	0 1	EACH	\$93.64 <u> </u>	\$3,021.78
16 - ELECTRICAL	7.1	- 4 0 1 1	CO4C 00	C4 540 46
Rough In Box, Plaster Ring & 20' of 3/4" EMT - St*Comp Ftgs & Branch Wire Rough In Box, Plaster Ring & 15' of 3/4" EMT - St*Comp Ftgs & Branch Wire		EACH EACH	\$216.88 \$173.01	\$1,518.16 \$8,477.49
		EACH	\$173.01 \$144.42	
Occupancy Sensor - Ceiling Mtd - Infrared - Self Contained Duplex Receptacle with Plastic Plate - Spec Grade - 20A			\$114.12 \$31.22	\$114.12 \$780.50
Occupancy Sensor - Wall Mtd - Infrared - with Switch		EACH EACH	\$57.48	\$780.50 \$229.92
2 Gang Iso-Gr. Duplex Receptacle with Plastic Plate - Spec Grade - 20A		EACH	\$90.44	\$361.76
Iso.Gr. Dbl. Duplex Receptacle with Hastic Hate - Spec Grade - 20A		EACH	\$341.79	\$341.79
Power Connection to Furniture / Partition - Power Pole		EACH	\$323.73	\$647.46
2' x 4' - 2 Lamp 3" Parabolic Fluorescent Lay In		EACH	\$151.45	\$454.35
2' x 4' - 3 Lamp 3" Parabolic Fluorescent Lay In		EACH	\$163.60	\$1,963.20
2' x 4' - 3 Lamp Commercial Direct / Indirect Fluorescent Lay In		EACH	\$260.50	\$1,042.00
Communication Rough-In Box - 25' of 3/4" EMT St-SS Ftgs & Pull String		EACH	\$186.14	\$1,302.98
Communication Connection Rough-In to Furniture - Poke Thru Floor Box		EACH	\$316.57	\$316.57
Communication Connection Rough-In to Furniture - Tele Pole		EACH	\$248.10	\$496.20
č			· · · · · · · · · · · · · · · · · · ·	\$18,046.50

**** REPORT TOTAL **** \$90,013.56

Project Labor Crew Report

Labor Group	Classification	Avg in Crew	Productivity	Base Rate	Burden 1	Burden 2	Total Rate	Rate X Qty
Crew Code:	CARP							
Carpenter	Foreman	1.0	60.00%	\$29.32	\$11.24	\$15.47	\$56.03	\$56.03
Carpenter	Journeyman	3.0	100.00%	\$28.31	\$11.24	\$15.09	\$54.64	\$163.92
Carpenter	Apprentice	1.0	100.00%	\$18.02	\$11.24	\$11.16	\$40.43	\$40.43
	Crew Totals	5.0	92.00%	Productive				\$260.38
				Con	nposite Rate	e Per Produ	ıctive Hour	\$56.60
Crew Code:	CARP	7						
Carpenter	Foreman	1.0	60.00%	\$29.32	\$11.24	\$15.47	\$56.03	\$56.03
Carpenter	Journeyman	3.0	100.00%	\$28.31	\$11.24	\$15.09	\$54.64	\$163.92
Carpenter	Apprentice	1.0	100.00%	\$18.02	\$11.24	\$11.16	\$40.43	\$40.43
	Crew Totals	5.0	92.00%	Productive				\$260.38
				Con	posite Rate	e Per Produ	ıctive Hour	\$56.60
Crew Code:	ELECT1	7						
Electricians	Foreman	1.0	60.00%	\$29.69	\$15.64	\$12.31	\$57.64	\$57.64
Electricians	Journeyman	3.0	100.00%	\$27.71	\$15.64	\$11.77	\$55.12	\$165.36
Electricians	Apprentice	1.0	100.00%	\$19.08	\$15.64	\$9.43	\$44.15	\$44.15
	Crew Totals	5.0	92.00%	Productive				\$267.15
				Con	nposite Rate	e Per Produ	ıctive Hour	\$58.08
Crew Code:	LABORER	7						
Labor	Journeyman	2.0	100.00%	\$25.20	\$10.44	\$13.95	\$49.59	\$99.18
Labor	Foreman	1.0	70.00%	\$26.61	\$10.44	\$14.51	\$51.56	\$51.56
Labor	Apprentice	1.0	100.00%	\$16.94	\$10.44	\$10.72	\$38.09	\$38.09
	Crew Totals	4.0	93.00%	Productive				\$188.83
				Con	nposite Rate	e Per Produ	ıctive Hour	\$50.76
Crew Code:	PAINT	٦						
Painters	Foreman	1.0	60.00%	\$29.77	\$10.18	\$13.65	\$53.59	\$53.59
Painters	Journeyman	3.0	100.00%	\$26.46	\$10.18	\$12.52	\$49.15	\$147.45
Painters	Apprentice	1.0	100.00%	\$17.69	\$10.18	\$9.52	\$37.38	\$37.38
	Crew Totals	5.0	92.00%	Productive				\$238.42
				Con	nposite Rate	e Per Produ	ıctive Hour	\$51.83

Project Labor Crew Report


Labor Group	Classification	Avg in Crew	Productivity	Base Rate	Burden 1	Burden 2	Total Rate	Rate X Qty
Crew Code:	SHTML							
Sheet Metal Workers	Apprentice	1.0	100.00%	\$18.40	\$14.18	\$10.80	\$43.38	\$43.38
Sheet Metal Workers	Foreman	1.0	60.00%	\$31.94	\$14.18	\$15.28	\$61.39	\$61.39
Sheet Metal Workers	Journeyman	3.0	100.00%	\$29.57	\$14.18	\$14.50	\$58.25	\$174.75
	Crew Totals	5.0	92.00%	Productive				\$279.52
				Con	nposite Rate	e Per Produ	uctive Hour	\$60.77
Crew Code:	TILE	7						
Ceramic Tile Layers	Apprentice	1.0	100.00%	\$17.46	\$10.60	\$8.74	\$36.80	\$36.80
Ceramic Tile Layers	Journeyman	3.0	100.00%	\$27.46	\$10.60	\$11.86	\$49.92	\$149.76
Ceramic Tile Layers	Journeyman	1.0	60.00%	\$27.46	\$10.60	\$11.86	\$49.92	\$49.92
	Crew Totals	5.0	92.00%	Productive				\$236.48
				Con	posite Rate	e Per Produ	uctive Hour	\$51.41

Kisent Corporation
Project: Interior Tenant Fit-Out Lombard, Illinois Date: 10/12/07

PROJECT RECAP & SUMMARY

Description	Unit Price Ext		
02 - SITEWORK	\$9,530.56	\$7.94	
06 - WOOD & PLASTICS	\$13,790.88	\$11.49	
07 - THERMAL & MOISTURE PROTECTION	\$840.00	\$0.70	
08 - DOORS AND WINDOWS	\$10,342.52	\$8.62	
09 - FINISHES	\$34,441.32	\$28.70	
15 - MECHANICAL	\$3,021.78	\$2.52	
16 - ELECTRICAL	\$18,046.50	\$15.04	
**** REPORT TOTAL ****	\$90,013.56	\$75.01	
======== SUMMARY ==========			
SUMMARY MARKUPS			
General Conditions, OH & P *** 15.00% of Total	\$13,502.03	\$11.25	
Contingencies *** 10.00% of Total	\$10,351.56	\$8.63	
MARKUP TOTAL	\$23,854.00	\$19.88	
ESTIMATE TOTAL	\$113,867.00	\$94.89	

Interior Tenant Fit-Out Percentage of Cost Report



1	02 - SITEWORK	\$9,530.56	10.6%
2	06 - WOOD & PLASTICS	\$13,790.88	15.3%
3	07 - THERMAL & MOISTURE PROTECTION	\$840.00	0.9%
4	08 - DOORS AND WINDOWS	\$10,342.52	11.5%
5	09 - FINISHES	\$34,441.32	38.3%
6	15 - MECHANICAL	\$3,021.78	3.4%
7	16 - ELECTRICAL	\$18,046.50	20.0%
	**** REPORT TOTAL ****	\$90,013.56	